BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

MODIFIED SCHEDULE - B

Package No-11

1.Providing Children playing equipments and gym equipments at Allalasandra Lake in ward No.04 of Yelahanka Division 2.Providing Children playing equipments and gym equipments in ward No.02,03 and 04 Yelahanka Division 3.Providing Grill Fencing to Selected parks in Ward No.02, 03 & 04 of Yelahanka Division 4.Providing Grill Fencing and Construction of Badminton court at Allalasandra Lake in Ward No.04 of Yelahanka Division 5.Providing Grill Fencing at Someshwara Hill lake in Ward No.03 of Yelahanka Division

SNo	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
1	807.15	Removing and resetting of kerb stones. complete as per specifications and directions of the Engineer in charge.	m	105.88	Rupees One Hundred Five And Paise Eighty Eight Only
2	558.58	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete., complete as per specifications and directions of the Engineer in charge.	m	436.98	Rupees Four Hundred Thirty Six And Paise Ninety Eight Only
3	96.00	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint complete as per specifications and directions of the Engineer in charge.	m	436.98	Rupees Four Hundred Thirty Six And Paise Ninety Eight Only
4	196.59	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. complete as per specifications and directions of the Engineer in charge.	Cum	5563.25	Rupees Five Thousand Five Hundred Sixty Three And Paise Twenty Five Only
	13.18	Above 125%		5563.25	Rupees Five Thousand Five Hundred Sixty Three And Paise
5	1391.47	Providing and applying painting in two coat with Synthetic enamel paint of approved brand and manufacture on concrete surface with cost of materials ,labour ,complete as per specifications.complete as per specifications and directions of the Engineer in charge.	Sqm	85.66	Rupees Eighty Five And Paise Sixty Six Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
6	476.36	Providing and laying heavy duty cobble stones 60mm thick interlock pavers,using cement and course sand for manufacturer of blocks of approved size,shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed(average Thinkness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to comeup in between joints , final compaction of pavers surfaces joint into its final level including cost of materials,labour and HOM complete as per specifications. complete as per specifications and directions of the Engineer in charge.	Sqm	1128.05	Rupees One Thousand One Hundred Twenty Eight And Paise Five Only
7	1.46	KSRRB M200-12.2. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. i) Lime /Cement Concrete. I. By Manual Means :B. Cement Concrete Grade M-15 & M-20. MORTH Specification. (5km lead = 57+2*1.28X5). complete as per specifications and directions of the Engineer in charge.	Cum	667.01	Rupees Six Hundred Sixty Seven And Paise One Only
8	958.20	Dismantling of barbed wire fencing / wire mesh fencing including posts, foundation concrete, back filling of pit by manual means including disposal of dismantled material with all lifts and stacking serviceable material and unserviceable material separately complete as per specifications. MORTH Specification. complete as per specifications and directions of the Engineer in charge.	m	71.23	Rupees Seventy One And Paise Twenty Three Only
9	274.82	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. complete as per specifications and directions of the Engineer in charge.	cum	4923.19	Rupees Four Thousand Nine Hundred Twenty Three And Paise Nineteen Only
10	189.45	Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:4 , edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, scaffolding, curing complete as per specifications.complete as per specifications and directions of the Engineer in charge.	Cum	6432.39	Rupees Six Thousand Four Hundred Thirty Two And Paise Thirty Nine Only
11	267.17	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications..complete as per specifications and directions of the Engineer in charge.	Sqm	152.08	Rupees One Hundred Fifty Two And Paise Eight Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
12	70.26	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.complete as per specifications and directions of the Engineer in charge.	Cum	5707.63	Rupees Five Thousand Seven Hundred Seven And Paise Sixty Three Only
13	47.50	Supplying and fixing M.S rectangular poles made out of two equal angles of 65X65X6 mm welded together and fixed in CC 1:2:4 with two numbers 16mm dia M.S hold fast rods each of length 25cms including cost of all materials cutting, bending scaffolding whereever necessary, nicely finishing the welded jonts with all lead lift and as per the direction of engineer incharge of the work and including providing two coats of approved quality paint over coat of shop painting (excluding cost of earthwork and concrete)..complete as per specifications and directions of the Engineer in charge.	m	920.15	Rupees Nine Hundred Twenty And Paise Fifteen Only
14	2181.15	Fabricating providing and erecting in position of MS Hot Dip galvanized sq hallow poles of 132 x132 heavy gauge length 3000mm with MS Hot Dip galvanized grill work as per approved design and drawing of chief architect using 12 x75mm galvanized flat for alround frame and 20 x 20mm galvanized forged ornamental arrow head in top and buttom the work is inclusive of throughing flat square rods placing welding all the joints including griding finishing 2 coats of anticorrossive paint over one coat of metal primer the rate is inclusive of all materials all items of work cost painting welding cutting griding with lead and lift as per specifications including loading and unloading with cost and conveyance of all materials labour machinery and incidental charges for the successful completion of the work as per direction of engineer in charge of work.	Sqm	9240.96	Rupees Nine Thousand Two Hundred Forty And Paise Ninety Six Only
15	115.20	Providing chain link fencing 50mm size of 8 guage properly stretched between rectangularpoleas and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour lead and lift and as per the directions of the engineer incharge of work including two coats of approved quality paint over one coat of shop paint. completion of the work as per direction of engineer in charge of work.	Sqm	765.19	Rupees Seven Hundred Sixty Five And Paise Nineteen Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
16	0.00	Providing and fixing M.S Gate as per Chief Architect Drawing , using 50mm x 50mm x 14 gauge M.S hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16mm x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40 mm x 6mm M.S flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc., complete. all the steel surface should be throughly cleaned free of rust and painted with anti materials , labour charges for all items of work , Hire charges for welding , cutting and grinding eqipment , electricity charges , with lead and lift , loading and unloading charges , etc.completion of the work as per direction of engineer in charge of work.	Sqm	3226.30	Rupees Three Thousand Two Hundred Twenty Six And Paise Thirty Only
17	48.70	Fabricating, providing and erecting in position Hot dip galvanized Gate. Using 72x72x4.8 mm Sq. G I Pipe Frame with top pipe bending in heavy duty hydraulic press with sand packing and hot bending to form double arch as per drawing profile, 20mm hot dip galvanized sq.rod for verticals at 150mm c/c , as shown in the drawing including providing hot do galvanized forged ornamental design in between rods and heads at top, middle and bottom. Intermediate supports of 75x12mm and 50x6mm arch bent to hot dip galvanized flats.The work is inclusive of throughing GI, Flat GI Sqm. rods, placing, welding all the joints including grinding, finishing metal patty, painting two coats enamel painting. The rate is inclusive of all materials Like GI Sq. GI Pipe, GI Forged designs etc., heavy duty hinges are made out of 75mm sold sq. block assembled with 20mm du bearing in three places for each flop. Heavy duty locking arrangement of low places including cost of labour, painting, erection charges using hoist pulley cranes, with all lead and lift, loading, trasportation, unloading, scaffolding charges and all other.completion of the work as per direction of engineer in	Sqm	12606.83	Rupees Twelve Thousand Six Hundred Six And Paise Eighty Three Only
18	192.00	Providing and applying enamel metal paint two coats (exclusive primer coat) over new steel or other metal surfaces brushing to give an shade after cleaning oil grease dirt and other forien matters including cost of materials labour complate as per specifications. completion of the work as per direction of engineer in charge of work.	Sqm	101.06	Rupees One Hundred One And Paise Six Only
19	38.47	PROVIDING TRAPEZOIDAL PROFILED SHEET Providing and installing of pre painted Galvolume iron Trapezoidal profiled sheet of approved make 1060 mm width (1000 mm cover width), 28-30 mm crest height with crest distance of 200 mm c/c with 2 ribs at the centre for stiffening. The total coated thickness (TCT) of the sheet will be 0.47 mm +/- 0.02 mm tolerance Zinc-Alu Alloy coating AZ150 gsm as per ASTM 1397/A755-550 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using self drilling/self tapping screws of 25 mm length, to be fixed over the existing purlins, rafters, channels and trusses.completion of the work as per direction of engineer in charge of work.	Sqm	736.31	Rupees Seven Hundred Thirty Six And Paise Thirty One Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
20	737.49	Earthwork excavation By manual means for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. (5km lead = 57+2*1.28X5). completion of the work as per direction of engineer in charge of work. (Qty upto 125%)	Cum	390.78	Rupees Three Hundred Ninety And Paise Seventy Eight Only
	16.98	Above 125%		390.78	Rupees Three Hundred Ninety And Paise Seventy Eight Only
21	356.25	Providing and filling sand in trenches to required depth including watring ramming with all leads and lift complete as per specifications and directed by the engineer incharge at the site.completion of the work as per direction of engineer in charge of work.(Qty upto 125%)	cum	2206.05	Rupees Two Thousand Two Hundred Six And Paise Five Only
	6.63	Above 125%		2206.05	Rupees Two Thousand Two Hundred Six And Paise Five Only
23	139.43	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, mortar including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification. completion of the work as per direction of engineer in charge of work.(Qty upto 125%)	Sqm	1319.59	Rupees One Thousand Three Hundred Nineteen And Paise Fifty Nine Only
	24.90	Qty Above 125%		1319.59	Rupees One Thousand Three Hundred Nineteen And Paise Fifty Nine Only
22	0.00	Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications..completion of the work as per direction of engineer in charge of work.	Sqm	976.94	Rupees Nine Hundred Seventy Six And Paise Ninety Four Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
24	2.00	Supply & fixing of children multi play equipment with spiral slide, monkey bar with number pannel .Upright structural posts of height 4.2 m are to be hot dip galvanized steel with a 114 mm OD and 2.2mm wall thickness of tubing . Roof of size 1.9m x 1.7m x 0.77 m , spiral slide of size2.56m x 1.85m x 2.68m. Top rails of monkey bar size 1.8m x 1.3m are all robotic welded & fabricated from 48mm OD galvanized steel pipes for the outer bars &32 mm OD galvanized steel for the inner parallel bars with a baked on powder coated finish. Deck of size 1.45 x 1.45 m are pressed and punched , welded ,sand blasted ,powder coated to 2.2mm thickness or vinyl coated to a thickness of 4mm . Deck of size 1.45 x 1.45 m are pressed and punched , welded ,sand blasted ,powder coated to 2.2mmthickness or vinyl coated to a thickness of 4mm. Deck, step, platform ,stairs, baffle shall be all robotic welded. Inclined ramps of size 1.92m x 0.65m , stair case of size 1.5m x 0.77m are fabricated from solid 2mm perforated solid punched steel Frisbee climber , piped walls of size 1 m are robotic welded , fabricated from 32 mm OD galvanized steelpipes for outer and 25mm OD galvanized steel pipes for inner bar with baked on powder coat finish.The poles	Each	1936256.44	Rupees Nineteen Lakh(s) Thirty Six Thousand Two Hundred Fifty Six And Paise Forty Four Only
25	1.00	Supply and fixing of childern Multi Play Equipment with double swing, curved side toddler slide with animated roof Upright structural posts of height 2.7 m and 3 m are to be schedule HOT DIP Galvanized steel with a 114mm OD and 2.2mm (wall) thickness of the tubing. The poles are welded on to a base plate made from steel with 114mm inner diameter. Deck of size 1.45 x 1.45m and Staircase of size 1.48 m x 0.60 m are fabricated from 2mm perforated solid punched steel. Deck perimeter is precision pre punched for attachments. Handrail of height 1.90 m and Dia 32 mm shall be an all-robotic welded unit, fabricated from 32 O.D. galvanized steel pipes with a baked on powder coating finish. Exposed hardware shall be covered with ultra violet stabilized plastic safety caps as per Sun Roof of size 2.0 m x 1.78 m x 0.77m, Spiral Slide of size 2220 mm x 1630 mm x 1880 mm , Straight Slide of size 1645 mm x 800 mm x 1140 mm, Panels. Roofs and panels are copyrighted and IP protected worldwide. Spring Climber of thickness Dia 38 mm, 3 step ladder , Frisbee Climber ,Piped walls of Height 2.7 m are all robotic welded fabricated from 32 O.D. galvanized steel pipes for the	Each	1229647.65	Rupees Twelve Lakh(s) Twenty Nine Thousand Six Hundred Forty Seven And Paise Sixty Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
26	1.00	Supply and fixing of childern Multi Play Equipment with curved slide and number panel : Upright structural posts of height 2.4 m, 2.7 m, 3.3 m schedule HOT DIP Galvanized steel with a 114mm OD and 2.2mm (wall) thickness of the tubing. All metal components are to be finished with a baked on powder coat finish.With deck of size 1.45 x 1.45m and Staircase of size 1.5m x 0.77 m are fabricated from 2mm perforated solid punched steel. Deck perimeter is precision pre punched for attachments. Decks are pressed, punched, and welded sand blasted and vinyl plastic coated to a thickness of 4mm. Along with Handrail of height 2.2 m and Dia 32 mm shall be an all-robotic welded unit, fabricated from 32 O.D. galvanized steel pipes with a baked on powder coating finish.Curved Slide of size 1.94 m x 1.85 m x 2.4 m, Panels,Toprails Of Monkey loop of size 1.8 m x 1.3 m.Deck of size 1.45 x 1.45m are fabricated from 2mm perforated solid punched steel. Deck perimeter is precision pre punched for attachments. Decks are pressed, punched, and welded sand blasted and vinyl plastic coated to a thickness of 4mm. Roof of size Dia 2 m and height 0.82 m, Spiral Slide of size 1.16 m x 1.6	Each	2224684.00	Rupees Twenty Two Lakh(s) Twenty Four Thousand Six Hundred Eighty Four Only
27	4.00	Supply and fixing of childern Multi Play Equipment :Upright structural posts of height 2.35 m , 3.0 m and 3.25 m are to be schedule HOT DIP Galvanized steel with a 114mm OD and 2.2mm (wall) thickness of the tubing. Handrail of height 2.20 m and Dia 32 mm shall be an all-robotic welded unit, fabricated from 32 O.D. galvanized steel pipes with a baked on powder coating finish. Snake Ladder Climber of size 0.99 m x 0.62 m x 1.20 m with thickness of Dia 38 mm, Piped walls of Height 2.6 m are all robotic welded fabricated from 32 O.D. galvanized steel pipes for the outer pipes and 25mm O.D. galvanized steel for the inner parallel bars with a baked on powder coat finish. crab Roof of size 1.9 m x 1.7 m x 0.77m, Sun Roof of size 2.0 m x 1.78 m x 0.77m, Straight slide 2.28 m x 0.83 m x 1.20 m , Spiral Slide of size 2.22 m x 1.60 m x 1.5 m, Rock climber of size 1.03 m x 0.70 m x 1.20 m Panel. The rates are to be inclusive of supply and installation at site. Inclusive of All Taxes and Transportation Charges..completion of the work as per direction of engineer in charge of work.	Each	1514825.81	Rupees Fifteen Lakh(s) Fourteen Thousand Eight Hundred Twenty Five And Paise Eighty One Only
28	4.00	Supply and fixing of childern Play Equipment Two seater seesaw : The See Saw consists of 2 poles of Dia 114mm and thickness of 2.5mm which balances the horizontal rod at the center which is of size 3110 mm length and Dia 114 mm. It consists of 2 seats which is made of LLDPE virgin plastic of size 305mm X 213 mm X 125 mm. The rates are to be inclusive of supply and installation at site. Inclusive of All Taxes and Transportation Charges.completion of the work as per direction of engineer in charge of work.	Each	84365.05	Rupees Eighty Four Thousand Three Hundred Sixty Five And Paise Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
29	1.00	Supply & fixing of Arm & Pedal Bike : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Each	214757.81	Rupees Two Lakh(s) Fourteen Thousand Seven Hundred Fifty Seven And Paise Eighty One Only
30	1.00	Supply & fixing of Big Shoulder Wheel : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Each	151593.75	Rupees One Lakh(s) Fifty One Thousand Five Hundred Ninety Three And Paise Seventy Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
31	1.00	Supply & fixing of Elliptical Cross Trainer: All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Each	176859.38	Rupees One Lakh(s) Seventy Six Thousand Eight Hundred Fifty Nine And Paise Thirty Eight Only
32	1.00	Supply & fixing of Pull Down Challenger : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Each	299145.00	Rupees Two Lakh(s) Ninety Nine Thousand One Hundred Forty Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
33	1.00	Supply & fixing of Seated Chest Press : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Each	290554.69	Rupees Two Lakh(s) Ninety Thousand Five Hundred Fifty Four And Paise Sixty Nine Only
34	1.00	Supply & fixing of Rider : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns.	Each	113695.31	Rupees One Lakh(s) Thirteen Thousand Six Hundred Ninety Five And Paise Thirty One Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
35	1.00	Supply & fixing of Tai Chi Spinners : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Each	145276.86	Rupees One Lakh(s) Forty Five Thousand Two Hundred Seventy Six And Paise Eighty Six Only
36	1.00	Supply & fixing of HD Sit Up Station : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Each	157909.68	Rupees One Lakh(s) Fifty Seven Thousand Nine Hundred Nine And Paise Sixty Eight Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
37	1.00	Supply & fixing of HD Squat Pushing : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Each	271604.99	Rupees Two Lakh(s) Seventy One Thousand Six Hundred Four And Paise Ninety Nine Only
38	1.00	Supply & fixing of HD Health Walker :All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out in excess of at least 50 public park projects in India either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance	Each	176859.38	Rupees One Lakh(s) Seventy Six Thousand Eight Hundred Fifty Nine And Paise Thirty Eight Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	uantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
39	1.00	Supply & fixing of HD Mini Ski :All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out in excess of at least 50 public park projects in India either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance to	Each	201215.44	Rupees Two Lakh(s) One Thousand Two Hundred Fifteen And Paise Forty Four Only
40	1.00	Supply & fixing of HD Waist Twister :All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out in excess of at least 50 public park projects in India either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance	Each	164226.56	Rupees One Lakh(s) Sixty Four Thousand Two Hundred Twenty Six And Paise Fifty Six Only
41	141.46	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clodscomplete as per specifications and directions of the Engineer in charge.(Qty upto 125%)	Cum	327.25	Rupees Three Hundred Twenty Seven And Paise Twenty Five Only
	339.09	Qty Above 125%		327.25	Rupees Three Hundred Twenty Seven And Paise Twenty Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
42	780.00	Bored / Cast-in-situ R.C.C. . piles with OPC cement design mix M20 @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.46cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 excluding reinforcement as per drawings including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH Specification complete as per specifications and directions of the Engineer in charge.(Qty upto 125%)	m	12344.06	Rupees Twelve Thousand Three Hundred Forty Four And Paise Six Only
	118.00	Qty Above 125%		12344.06	Rupees Twelve Thousand Three Hundred Forty Four
43	7.53	Providing and laying in position plain cement concrete of mix 1:4:8(M7.5)with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregtes @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.complete as per specifications and directions of the Engineer in charge.	Cum	5568.06	Rupees Five Thousand Five Hundred Sixty Eight And Paise Six Only
	1.56	Qty Above 125%		5568.06	Rupees Five Thousand Five Hundred Sixty Eight And Paise Six
44	122.31	Providing and laying in position plain cement concrete of mix M15 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation,plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. complete as per specifications and directions of the Engineer in charge.	Cum	5917.45	Rupees Five Thousand Nine Hundred Seventeen And Paise Forty Five Only
45	2.13	Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1:6, stone hammerddressed in courses not less than 20 cms high, bond stones at 2m apart in each course including cost of materials, labour, curing complete as per specifications and directions of the Engineer in charg	Cum	5015.59	Rupees Five Thousand Fifteen And Paise Fifty Nine Only
	4.12	Qty Above 125%		5015.59	Rupees Five Thousand Fifteen And Paise Fifty Nine Only
46	31.61	Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications.complete as per specifications and directions of the Engineer in charge.(Qty upto 125%)	Cum	219.45	Rupees Two Hundred Nineteen And Paise Forty Five Only
	61.43	Qty Above 125%		219.45	Rupees Two Hundred Nineteen And Paise Forty Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
	0.00	Conveying the excavated earth, debries etc., with all lead and lifts including loading and unloading charges etc., complete as per the direction of the Engineer-in-charge.	Cum	67.38	Rupees Sixty Seven And Paise Thirty Eight Only
48	95.04	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons. complete as per specifications and directions of the Engineer in charge.	Sqm	281.05	Rupees Two Hundred Eighty One And Paise Five Only
49	266.01	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness , including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons. complete as per specifications and directions of the Engineer in charge.	Sqm	389.81	Rupees Three Hundred Eighty Nine And Paise Eighty One Only
50	17.00	Providing and removing centering, shuttering, strutting, propping etc. and Removal of form Work for columns, pillars, piers, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specificaiton. complete as per specifications and directions of the Engineer in charge.(Qty upto 125%)	Sqm	497.61	Rupees Four Hundred Ninety Seven And Paise Sixty One Only
	89.56	Qty Above 125%		497.61	Rupees Four Hundred Ninety Seven And Paise Sixty One Only
51	67.32	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for suspended floors, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specificaitons for heights more than 3.50m from ground level. - 0 to 5 mtrs.complete as per specifications and directions of the Engineer in charge.	Sqm	436.01	Rupees Four Hundred Thirty Six And Paise One Only
52	9.00	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floors including cost of all materials,labour complete as per specifications. complete as per specifications and directions of the Engineer in charge.	Sqm	823.90	Rupees Eight Hundred Twenty Three And Paise Ninety Only
	11.57	Qty Above 125%		823.90	Rupees Eight Hundred Twenty Three And Paise Ninety Only
53	89.49	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specificaitons.complete as per specifications and directions of the Engineer in charge.	Sqm	318.59	Rupees Three Hundred Eighteen And Paise Fifty Nine Only

Contractor

15

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
54	0.00	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specificaitons.complete as per specifications and directions of the Engineer in charge.	Sqm	352.28	Rupees Three Hundred Fifty Two And Paise Twenty Eight Only
55	80.15	Providing and laying in position reinforced cement concrete of Design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70 cum and fine aggregtes @ 0.47cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. complete as per specifications and directions of the Engineer in charge.(Qty upto 125%)	Cum	6342.88	Rupees Six Thousand Three Hundred Forty Two And Paise Eighty Eight Only
	5.63	Qty Above 125%		0.00	Rupees Nil
56	29.68	Providing and laying in position reinforced cementconcrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum andfine aggregtes @ 0.47cum,with superplastisiser @3lts confirming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick,vibrated fo all works in ground Floor level for roof slabs ,staircase, lintels , beams, retaining walls ,return wall, walls (an thivck ness) including attached plasters ,columns, pillars,posts,struts.butters,string or lacing courses ,parapets,coping,bed blocks,anchor blocks ,plain window cills,fillets including cost of all materials, labour,HOM of machinery, curing, complete as per complete as per specifications and directions of the Engineer in charge.	Cum	6597.94	Rupees Six Thousand Five Hundred Ninety Seven And Paise Ninety Four Only
	9.88	Qty Above 125%		6597.94	Rupees Six Thousand Five Hundred Ninety Seven And Paise
57	4.54	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 27.20kgs, with 12mm and down size graded granite metal coarse aggregates @0.5865cum and fine aggregtes @ 0.391cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 8.5 cms. average thickness, upto First Floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications.complete as per specifications and directions of the Engineer in charge.	Sqm	540.93	Rupees Five Hundred Forty And Paise Ninety Three Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
			In figures	In words
33.13	Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. complete as per specifications and directions of the Engineer in charge.(Qty upto 125%)	tonne	77457.19	Rupees Seventy Seven Thousand Four Hundred Fifty Seven And Paise Nineteen Only
4.34	Qty Above 125%		77457.19	Rupees Seventy Seven Thousand Four Hundred Fifty Seven
596.29	Providing and constructing load bearing wall with solid concrete blocks of size 400X200X200mm having block density not less than 1800kg/m3 having a minimum average compressive strength 5.00N/mm2 confirming to IS 2185 (part 1) :2005 and constructed with cement mortar 1:4,as per IS 2572:2005 including cost of materials, labour charges, scaffolding, curing, hire charges of machinaries etc., complete as per specifications.complete as per specifications and directions of the Engineer in charge.	Sqm	995.23	Rupees Nine Hundred Ninety Five And Paise Twenty Three Only
49139.00	Fabrication supplying and erecting M.S. tubular trusses of all spans with prefabricated steel applications using quality material and are durable, reliable and corrosion and abrasion resistant. Welding shall confirm to latest structural welding code. Quality shall be on various parameters like shape, size, design gauge and polish. The entire trusses is anchored in RCC column by using 4 nos of M.S. anchor bolts at each support with 10mm thick base plate and shoe plate. The work includes cutting, straightening, placing in position of M.S. pipes and welding wherever necessary and applying one coat of redoxide primer coat to all the. members including cost of all materials, labour charges, and hire charges of machineries for cutting, welding, grinding and erection equipments, with all lead and lift, transportation, complete as per specifications and directions of the Engineer in charge.	kg	120.31	Rupees One Hundred Twenty And Paise Thirty One Only
4117.07	Qty Above 125%		120.31	Rupees One Hundred Twenty And Paise Thirty One Only
308.23	Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications.(Including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density) MORTH Specification complete as per specifications and directions of the Engineer in charge.	cum	354.20	Rupees Three Hundred Fifty Four And Paise Twenty Only
235.85	Qty Above 125%		354.20	Rupees Three Hundred Fifty Four And Paise Twenty Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-63

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
62	0.00	Providing and constructing non-load bearing wall with solid concrete blocks of size 400X100X200 having a block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 conforming to I.S : 2185 (Part 1) : 2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials, labour charges, scaffolding, curing, hire chargesof machineries etc., complete as per specifications. complete as per specifications and directions of the Engineer in charge.	Sqm	885.50	Rupees Eight Hundred Eighty Five And Paise Fifty Only
63	478.36	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners. wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications complete as per specifications and directions of the Engineer in charge.	Sqm	283.94	Rupees Two Hundred Eighty Three And Paise Ninety Four Only
64	631.21	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications .complete as per specifications and directions of the Engineer in charge.	Sqm	222.34	Rupees Two Hundred Twenty Two And Paise Thirty Four Only
65	115.24	Providing rough cement plastering 15mm thick in single coat with cement mortar 1:4 to brick masonry for base of dadooing works with sand of approved quality, providing and removing scaffolding, inclding cost of materials, labour, curing complete as per specifications complete as per specifications and directions of the Engineer in charge.	Sqm	223.30	Rupees Two Hundred Twenty Three And Paise Thirty Only
	14.36	Qty Above 125%		223.30	Rupees Two Hundred Twenty Three And Paise Thirty Only
66	61.20	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to ceiling including rounding off corners wherever required smooth rendering, : including Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.complete as per specifications and directions of the Engineer in charge.	Sqm	245.44	Rupees Two Hundred Forty Five And Paise Forty Four Only
67	574.62	providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty . Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers, including cost of alll mateerial cost of labour and scaffolding etc. ,complete as per specification.complete as per specifications and directions of the Engineer in charge.	Sqm	84.70	Rupees Eighty Four And Paise Seventy Only
68	631.21	Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. - with primer. complete as per specifications and directions of the Engineer in charge.	Sqm	98.18	Rupees Ninety Eight And Paise Eighteen Only

Contractor

18

Executive Engineer
Project Division
Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
69	74.25	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications page no117 item no 15.49.1 . KSRB 15-14.1 : Extra over Item 15-14.1 for applying oil bound washable distemper on ceiling and / or sloping roof as per specifications.complete as per specifications and directions of the Engineer in charge.	Sqm	128.01	Rupees One Hundred Twenty Eight And Paise One Only
	363.28	Qty Above 125%		128.01	Rupees One Hundred Twenty Eight And Paise One Only
70	478.36	Providing external walls with texture finish using approved brand paint, applied uniformly in three coats over one coat of primer including cost of all materials, machineries, labour, transportation, loading and unloading, all lead and lift and all other incidental charges including scaffolding and removing stains, complete as per specifications complete as per specifications and directions of the Engineer in charge.	Sqm	370.56	Rupees Three Hundred Seventy And Paise Fifty Six Only
71	295.31	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approve design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications and directions of the Engineer in charge.	kgs	102.99	Rupees One Hundred Two And Paise Ninety Nine Only
	821.89	Qty Above 125%		102.99	Rupees One Hundred Two And Paise Ninety Nine Only
72	754.80	Providing and laying M-15 cement concrete flooring, 50 mm thick with metallic concrete hardner topping , under layer of 35mm thick m-15 cement concrete using broken granite metal of 20mm and down size, and top layer 50mm thick of metallic cement hardner consisting of mix 1:2 (1 cement hardner mix : 2 granite metal 10mm nominal size) by volume, with which metallic hardening compound of approved quality mix in the ratio of 4:1 (4 part of cement and 1 part of metallic floor hardening compound of approved quality by wt) , including finishing cost of materials, labour, curing, complete as per specifications and directions of the Engineer in charge.	Sqm	688.19	Rupees Six Hundred Eighty Eight And Paise Nineteen Only
73	13.75	Providing and fixing for flooring 20mm thick gang saw water cut sadarhalli gray granite in CM 1:4 proportion, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, groves in joints including cost of curing - minimum width of 900mm.complete as per specifications and directions of the Engineer in charge.	Sqm	2159.85	Rupees Two Thousand One Hundred Fifty Nine And Paise Eighty Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
74	35.65	Providing and fixing Vetrified glazed tiles of approved make quality & colour of size 900x900x 12mm thick fixed on bed of 12mm thick cement mortar for flooring ,skirting ad jointed with neat cement slurry mixed with pigment to match shade of tiles, including providing spacers at required interval and removing stains etc including Cost of all materials mortar labour etc complete as per specifications and directions of the Engineer in charge.	Sqm	1240.66	Rupees One Thousand Two Hundred Forty And Paise Sixty Six Only
	126.67	Qty Above 125%		1240.66	Rupees One Thousand Two Hundred Forty And Paise Sixty Six Only
75	8.70	Providing Ceramic tiles of size 30x30cms 6mm thick of approved make ,shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment , including cost of materials, labour, curing, complete as per specifications and directions of the Engineer in charge.	Sqm	1320.55	Rupees One Thousand Three Hundred Twenty And Paise Fifty Five Only
	93.80	Qty Above 125%		1320.55	Rupees One Thousand Three Hundred Twenty And Paise Fifty Five
76	109.20	Providing skirting, dado, rises of steps with colour glazed tiles 30X60 cms 6mm thick with border of size 30 x 10 cms on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications and directions of the Engineer in charge.	Sqm	1780.63	Rupees One Thousand Seven Hundred Eighty And Paise Sixty Three Only
	65.64	Qty Above 125%		1780.63	Rupees One Thousand Seven Hundred Eighty And Paise Sixty Three
77	2.00	Providing half nosing for 20mm thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, HOM of equipment etc., complete as per specification and directions of the Engineer in charge.	Sqm	196.35	Rupees One Hundred Ninety Six And Paise Thirty Five Only
	14.50	Qty Above 125%		196.35	Rupees One Hundred Ninety Six And Paise Thirty Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner